MOHANTY ELECTRICAL

At: Khundeibenta Sahi, , MO - 9777966308

Estimate & Quotation Bill

Ref. No.: ..... Date: .....

To

The Managing Director,
Odisha Knowledge Corporation Ltd.,
Bhubaneswar.

Subject: Verification report of ICT lab

Dear Sir,

We are a registered contractor ***NARAYAN CHANDRA MOHANTY*** an approved Electrical contractor of Government of Odisha, bearing Licence No. ***BBS/PU-1407*** for your kind perusal.

After verification of the following items of the ICT lab at AISHANESWAR DHANDAMULAK BIDYAPITH UDISE CODE: 21180204003 BRAHMAGIRI, ***PURI*** as per the minimum specification mentioned below, the report for the same is being attached.

Sr. No.	Item name	Minimum Specifications	Quantity
1	Earthing (as per IS specifications)	Copper plate earthing stations making earthing with copper earth plate	1
		600 mm x 600 mm x 3 mm thick including funnel, charcoal/coke, salt, all earth work.	
2	Switches and sockets (ISI Mark)	5 A- 240 V switches	15
		2 in 1 5A and 15A Sockets	15
		15 A – 240 V socket with shutter	2
		Indicative Brands: - Anchor / Havells / crabtree /Wipro /Phillips / Legrand (Pls. tick) Switches and sockets is to be provided for all electronics/IT equipment including printer and Projection System to be placed at lab technician table	
3	Wiring (ISI Mark)	PVC conduits including MS/GI boxes. All wires should be covered, insulated and properly clamped. Wiring for 5 and 15A power outlets with 4 square mm PVC insulated stranded copper conductor wires Earthing of 3rd pin with PVC insulated green color 2.5 square mm copper wire	Full Lab

Narayan Chandra Mohanty

With regards

Narayan Chandra Mohanty

GOVERNMENT OF ORISSA

ELECTRICAL WORKMEN'S PERMIT

DEPARTMENT OF ENERGY

Date of renewal	Date of Expiry	Signature of Electrical Inspector
08-05-2007	07-05-2012	
04.05.2012	07.05.2017	

19

Photograph of Permits Holder

This permit is to be carried on the holder's person